Pittsburg County, Oklahoma COUNTY PURCHASING OFFICE

Pittsburg County Court House McAlester, Oklahoma Phone: (918) 423–4934

INVITATION TO BID

PLEASE REVIEW TERMS AND CONDITIONS ON REVERSE SIDE RELATING TO SUBMISSION OF THIS BID. Notarized Affidavit completions and signature required on reverse side.				DATE ISSUED 22-Jan-13 PAGE 1 OF	
BID NUMBER Bid # 11			BID CLOSING DATE AND HOUR February 4, 2013 @ 10:00AM	REQUIRED DELIVERY DATE Days after award of Purchase Order	
TERMS:				DATE OF DELIVERY:	
Item	Quantity	Unit of issue	DESCRIPTION	Unit Price	Total
		issue	Pittsburg County Commissioners wishes to advertise for the following for the Tannehill Volunteer Fire Department: Construction of a 60' x 70' Fire Station Building SEE SPECIFICATIONS ATTACHED.		I Old

RESOLUTION To Advertise

The Board of County Commissioners, Pittsburg County, met in regular session on Tuesday, January 22, 2013.

WHEREAS, the Board of County Commissioners, Pittsburg County, wishes to advertise for the following for the Tannehill Volunteer Fire Department:

Construction of a 60' x 70' Fire Station building

A bid package containing complete specifications and an "Invitation to Bid" are available at the Pittsburg County Clerk's Office, 115 East Carl Albert Parkway, Room 103, McAlester, Oklahoma 74501 or online at pittsburg.okcounties.org.

THEREFORE, each competitive bid submitted to the County must be accompanied with an affidavit for filing with the competitive bid form, as required by 61 O.S. \$ 138.

Sealed bids will be received and filed with the Pittsburg County Clerk and opened on February 4, 2013 at 10:00 a.m. in the Board of County Commissioners Conference Room, Pittsburg County Courthouse, 115 East Carl Albert Parkway, McAlester, Oklahoma. Contract will be awarded to the lowest or best bidder. The Board of County Commissioners reserves the right to reject any and all bids and re-advertise.

BOARD OF COUNTY COMMISSIOENRS PITTSBURG COUNTY, OKLAHOMA

VICE-CHAIRMAN

ATTEST:

by stope Jannell

SPEC SHEET FOR TANNEHILL BUILDING AT SCIPIO

The following are the specs for the building Tannehill Fire Dept wishes to build:

60' X 70' Pole barn type building with 14' sidewall height

4 each 12' X12' insulated steel overhead doors

1 each 3'0" X 6'8" walking steel door

6" concrete reinforced slab 60'X70'

Building is to be insulated with 2" commercial grade insulation

Post will be treated 6 X 6 10 ft. OC

29 Gauge colored metal

Metal will attached with screws- No nails

Top plate will be double 2 X 12

Trusses will be 2 X 6, 5' OC, 4/12 pitch, tied together with 2 X 4 stringers at the bottom

Girts will be 2 X 6

Purlins will be 2 X 4

NO Skylights

Building will be pre-engineered with drawings.

Rough IN plumbing and electrical will be provided prior to concrete work by Tannehill Fire Dept.